

---

<b>Addendum Number</b>	5
Addendum Date of Issue	April 06, 2021
RFP Number	21027 PP
RFP Description	Mechanical Retrofit (BAS, Secondary Pump, In-Suite Control Valves & DHW) – 3101 Weston Rd.
Page(s):	1
Attachment(s):	n/a

---

This Addendum forms part of the above mentioned RFP document and is to be read, interpreted, and coordinated with all other parts. The following revisions supplements and/or supersedes the information contained in the original RFP documents issued on March 09, 2021 for the above-named project to the extent referenced and shall become part thereof.

## **1. QUESTIONS AND ANSWERS**

1. Could you please provide location and panel schedule for LP-P1 panel. Scope of work on 1.1.2 Drawing E-102 refers to J+B Drawing E-101 but it is missing.

**A: The panel LP-P1 is being installed as part of the heating pump upgrades and is located in the boiler room (Panel is to be located to the left of the existing splitter SP1 as depicted on drawing E-102). All connected loads for the panel LP-P1 are shown on the E-102 SLD drawing (the three loads which are lighter in colour are existing / part of the heating pump upgrades).**

## **2. CLARIFICATIONS**

- a. New remote thermostat to be based on DANFOSS RA 2000 (013G8568 - 26') or approved equal. The location of the new thermostats is the same as the existing thermostat's location.

All other terms and conditions remain the same.

Amanda Abbott  
Sourcing Manager, Strategic Procurement

[End of Addendum #5]